



GOVERNMENT OF WEST BENGAL
WATER RESOURCES INVESTIGATION & DEVELOPMENT DEPARTMENT
OFFICE OF THE ASSISTANT ENGINEER (AGRI-MECH)
ALIPURDUAR (AGRI – MECHANICAL) SUB – DIVISION
NETAJI ROAD, DIST: ALIPURDUAR

NOTICE INVITING TENDER NO. - 02 OF 2022-23

Sealed Tenders in prescribed proforma W.B.F.-2911 (ii) are invited by the Assistant Engineer (A-M) Alipurduar (A-M) Sub-Division, Alipurduar on behalf of Governor of West Bengal for *REPAIRING OF PUMP HOUSE OF MADHYA RANGALIBAZNA GOVT OWNED AND OPERATED MAJOR RLI (E) SCHEME IN THE DISTRICT OF ALIPURDUAR UNDER JALPAIGURI (AM) DIVISION* from bonafide and resourceful contractors having sufficient experience and credential as mentioned therein in similar type of works.

1. REQUEST FOR TENDER DOCUMENTS:

Request for tender documents in the agency's letter head along with supporting documents [I) Latest Professional Tax Clearance Certificate II) GST registration certificate III) Latest Income Tax Return IV) PAN Card V) TRADE LICENSE requisite credential of similar type of works of at least 40 % of the estimated amount put to tender in a single work order during the last 5 years including current financial year] in original and photo copies (Self Attested), have to be submitted to the office of the Assistant Engineer (A-M), Alipurduar (A-M) Sub-Division, Alipurduar upto 02:00 p.m. of 17.10.2022. Original documents will be returned after verification.

2. SALE OF TENDER DOCUMENTS:

The tender documents shall be made available for sale at the office of the undersigned upto 4:00 p.m. of 17.10.2022 free of cost. Tender documents are not transferable.

3. EARNEST MONEY DEPOSIT:

Earnest money to be deposited along with the tender documents shall be in favour of the Executive Engineer (A-M), Jalpaiguri (A-M) Division in the form of Treasury Challan, Demand Draft, Banker's Cheque, Call deposit, Pay order on any Nationalized Bank payable at Jalpaiguri, validity period of which should be not less than 90 days from the date of opening of tender.

4. SUBMISSION OF TENDER:

Sealed envelop containing properly filled in tender documents along with earnest money and documents of Credentials and superscripting N.I.T. No., and addressed to the undersigned shall have to be deposited in the tender box, kept in the chamber of the undersigned up to 2:00 p.m. on 21.10.2022.

5. OPENING OF TENDER:

Tenders will be opened by the tender inviting authority or his representative in presence of the attending tenderers or their authorized representatives at his office after 4.00 p.m. on 21.10.2022. If, the date of opening of tender be declared as public holiday for any administrative reason(s), the tenders shall be opened on the next working day at the same time and place.

6. VALIDITY OF TENDER:

The bid shall remain valid normally for twelve months from the date of opening of tender.

7. TIME FOR COMPLETION:

Time for completion of the work shall be 30 days from the date of Work Order / Lay out.

8. PROCEDURE FOR QUOTING RATES:

The rate should be quoted clearly in figure and in words in percentage basis, i.e., Less, at par, above on the estimate cost put to tender at the space provided for the purpose in the WBF 2911(i/ii).

9. EXECUTION OF AGREEMENT :

The successful bidders shall have to execute formal Agreement with Executive Engineer (Agri-Mech), Jalpaiguri (Agri-Mech) Division within 10 (ten) days from the date of issue of acceptance and formal work order with deposition of initial security deposit @ 2% of the value of work. Another 8% will be deducted from the agency's progressive bills so as to make it a total 10% Security deposit. The agreement shall be made in duplicate in W B Form no. 2911 on realization of price of two sets of tender document by online payment through GRIPS portal under the head of 0702-80-800-002-27-other items- other receipt as per Annexure-I from the office of the Executive Engineer (A-M), Jalpaiguri (A-M) Division (non-refundable). Failing to execute formal agreement within stipulated time, the formal work order will be treated as cancelled.

10. DEDUCTION OF TAX: -

Taxes will be deducted from the progressive bill as per Government rule in vogue.

11. SPECIAL ATTENTION:

Earnest Money of unsuccessful bidders will be released after finalization of tender. Security deposit of successful bidder will be released after six months from the date of successful completion of the work recommended by the concerned Assistant Engineer (Agri-Mech). The tender inviting authority reserve the right to accept or reject any tender or split the work without assigning any reason whatsoever. Canvassing in any form will render oneself disqualify from participating the tender.

Sdf A. Saha

Assistant Engineer (A-M)
Alipurduar (A-M) Sub-Division,
Alipurduar

Memo No: 184 / (8)

Dated 11.10.2022.

Copy forwarded for information and wide circulation to: -

1. The Superintending Engineer (A-M), Siliguri (A-M) Circle, Shibmandir, Siliguri
2. The Executive Engineer (A-M), Jalpaiguri (A-M) Division, Jalpaiguri.
3. The Assistant Engineer (A-M) Siliguri / Jalpaiguri (A-M) Sub-Division, Siliguri / Jalpaiguri.
4. The Sabhadhipati, Alipurduar Zilla Parisad, Aipurduar.
5. The District Magistrate, Alipurduar.
6. The District Information & Culture Officer, Alipurduar
7. The D.I.O, Alipurduar. He is requested to upload a copy of this N.I.T. in the web portal.
8. Notice Board of this office.

Sdf A. Saha

Assistant Engineer (A-M)
Alipurduar (A-M) Sub-Division,
Alipurduar

ANNEXURE-I

Issued to:

(NIT NO: 02 OF 2022-23 OF THE ASSISTANT ENGINEER (A-M), ALIPURDUAR (A-M) SUB-DIVISION)

(Circulated vide office memo no: 184 dated 11.10.2022 of AE(AM), Alipurduar(AM) Sub-Division)

SI No	Name of Work	Estimated cost put to Tender	Token earnest money to be deposited	cost of tender documents during agreement (In Rs.)	Last date & time of application	Last date & time of selling of tender documents	Last date & time of submission of tender/ opening of tender	Completion Time	Minimum credential
1	2	3	4	5	6	7	8	9	10
1	REPAIRING OF PUMP HOUSE OF MADHYA RANGALIBAZNA GOVT OWNED AND OPERATED MAJOR RLI(E) SCHEME IN THE DISTRICT OF ALIPURDUAR UNDER JALPAIGURI (AM) DIVISION	Rs. 79,248.00	Rs. 2,000.00	Rs. 255.00	17.10.2022 upto 02:00 PM	17.10.2022 upto 04:00 PM	21.10.2022 upto 2:00 PM	30 (Thirty) days from the date of Layout	Rs. 32,000.00



Assistant Engineer (AM)
Alipurduar (AM) Sub-Division
Alipurduar

ANNEXURE-II

NIT NO: 02 OF 2022-23 OF THE ASSISTANT ENGINEER (A-M), ALIPURDUAR (A-M) SUB- DIVISION

Issued to:

**SCHEDULE FOR REPAIRING OF PUMP HOUSE OF MADHYA RANGALIBAZNA GOVT OWNED AND OPERATED MAJOR RLI(E) SCHEME IN THE
DISTRICT OF ALIPURDUAR UNDER JALPAIGURI (AM) DIVISION.**

SL No	Description of Item	Unit	Quantity	Rate In Rs.	Amount in Rs.				
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. (PWD-2017/P-11/ Item No-10)	m ²	200.00	19.00	3800.00				
2	Dismantling all types of plain cement concrete works , stacking serviceable materials at site and removing rubbish as directed with in a lead of 75m. In Ground floor(a) Up to 150 mm. thick (PWD-2017/P-10/It-2(a))	m ³	2.00	939.00	1878.00				
3	Plaster (to wall, floor ceiling etc) with sand and cement mortar including rounding off or chamfering corners, as directed and racking out joints or roughening of concrete surface including throating, nosing and drip course as necessary at ground floor. (PWD-2017/P-189/ Item No-1(ii))	(i) with (1:4) cement mortar.							
		(b) 20 mm. thick plaster.	m ²	50.00	177.00	8850.00			
		(c) 15 mm thick plaster	m ²	60.00	154.00	9240.00			
4	Cement concrete with 30mm down graded shingles (excluding shuttering) in ground floor. (PWD-2017/P-23/ Item No-1(a))								
	(a) (1:3:6 proportion)	m ³	2.00	4210.00	8420.00				
5	Ordinary Cement concrete (mix 1:2:4) with graded stone chips(20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes..PWD-2017/P-24/Item	m ³	2.50	3925.00	9812.50				
6	Labour for taking out door and window frame including shutter for repair and replacement of different parts of the frame & refixing the same including mending good all damages complete .(Concrete and brick work for mending damage will be paid separately)(PWD-2017/P-113/ Item No-20)	m ²	9.72	128.00	1244.16				
9	M.S. gate of Jail type as per approved design made of strong M.S.frame work, intermediate stiffeners and round / square bars or angles. M.S. sheet (not less than 14 gauge) gussets, cleats etc.including necessary riveting, bolting, welding, locking and hanging arrangements, fitting and fixing complete as per direction of the Engineer-in -charge. PWD-2017/P-105/Item no. 16.	Qtl.	2.00	7693.00	15386.00				
10	Supplying, fitting and fixing M.S. Clamp for fixing door and window frames made of flat bent bars end bifurcated including cutting brick work, fixing in cement concrete with stone chips (1:2:4) fitted and fixed as per direction and mending all damages complete. a) 40mm x 6mm x 250mm long.(PWD-2017/P-140/ Item No-4(a))	Nos	32.00	29.00	928.00				
11	Iron hasp bolt of approved quality (oxidised) with 16mm dia and 200mm long rod with centre bolt and round fitting.PWD/P-141/item no. 10(I)(a)								
		2	x 2	= 4	Each	2.00	134.00	268.00	
12	Supplying, fitting and fixing iron butt hinges of approved quality for door and window shutters with steel screw, with ISI mark.								
		(a) 10 cm long X 5.8 cm X 1.9mm	3	x 6	= 18	Each	18.00	47.00	846.00
		(PWD-2017/P-140/Item no. 5(vii)).							
	(b) 7.5 cm. long X 4.7cm.X 1.7mm	4	x 4	= 16	Each	16.00	31.00	496.00	
	PWD-2017/P-140/item no. 5(iv).								
12	Iron socket bolt of approved quality fitted and fixed complete.								
		(a) 22.5 cm. long (12 mm. dia.Bolt)	2	x 6	= 12	Each	12.00	77.00	924.00
		PWD-2017/P-141/Item no. 8(d).							
	(c) 10cm. long (10 mm. dia. Bolt)	2	x 7	= 14	Each	14.00	40.00	560.00	
	PWD-2017/P-141/item no. 8(b).								
13	Iron door ring of approved quality fitted and fixed with nuts and washers or screws as necessary.								
		(b) 50 mm dia			Each	6.00	17.00	102.00	
	PWD-2017/P-143/item no.24								
14	Neat cement punning about 1.5 mm. thick in wall dado, floor, drain, door and window sill etc. complete. PWD-2017/P-192/Item no. 15	m ²	110.00	34.00	3740.00				
					Total =	66494.66			
					Add 18 % GST	11969.04			
					Sub Total	78463.70			
					Add 1% labour cess	784.64			
					Total	79248.34			
					Say	79248.00			
RUPEES SEVENTY NINE THOUSAND TWO HUNDRED FORTY EIGHT ONLY									
	 11.10.22								
	Junior Engineer(M)								
	Alipurduar(AM) sub division					Assistant Engineer(AM)			
	Alipurduar					Alipurduar(AM) sub division			
						Alipurduar			