



GOVERNMENT OF WEST BENGAL  
WATER RESOURCES INVESTIGATION & DEVELOPMENT DEPARTMENT  
OFFICE OF THE ASSISTANT ENGINEER (AGRI-MECH)  
ALIPURDUAR (AGRI – MECHANICAL) SUB – DIVISION  
NETAJI ROAD, DIST: ALIPURDUAR

**NOTICE INVITING TENDER NO. – 03 OF 2022-23**

Sealed Tenders in prescribed proforma W.B.F.-2911 (ii) are invited by the Assistant Engineer (A-M) Alipurduar (A-M) Sub-Division, Alipurduar on behalf of Governor of West Bengal for *REPAIRING OF PIPE LINE OF DC II OF DAKSHIN KAMSING GOVT. OWNED AND OPERATED MAJOR RLI SCHEME IN THE DISTRICT OF ALIPURDUAR UNDER JALPAIGURI(A-M) DIVISION* from bonafide and resourceful contractors having sufficient experience and credential as mentioned therein in similar type of works.

**1. REQUEST FOR TENDER DOCUMENTS:**

Request for tender documents in the agency's letter head along with supporting documents [ I) Latest Professional Tax Clearance Certificate II) GST registration certificate III) Latest Income Tax Return IV) PAN Card V) TRADE LICENSE requisite credential of similar type of works of at least 40 % of the estimated amount put to tender in a single work order during the last 5 years including current financial year] in original and photo copies (Self Attested), have to be submitted to the office of the Assistant Engineer (A-M), Alipurduar (A-M) Sub-Division, Alipurduar upto 02:00 p.m. of 17.10.2022. Original documents will be returned after verification.

**2. SALE OF TENDER DOCUMENTS:**

The tender documents shall be made available for sale at the office of the undersigned upto 4:00 p.m. of 17.10.2022 free of cost. Tender documents are not transferable.

**3. EARNEST MONEY DEPOSIT:**

Earnest money to be deposited along with the tender documents shall be in favour of the Executive Engineer (A-M), Jalpaiguri (A-M) Division in the form of Treasury Challan, Demand Draft, Banker's Cheque, Call deposit, Pay order on any Nationalized Bank payable at Jalpaiguri, validity period of which should be not less than 90 days from the date of opening of tender.

**4. SUBMISSION OF TENDER:**

Sealed envelop containing properly filled in tender documents along with earnest money and documents of Credentials and superscripting N.I.T. No., and addressed to the undersigned shall have to be deposited in the tender box, kept in the chamber of the undersigned up to 2:00 p.m. on 21.10.2022.

**5. OPENING OF TENDER:**

Tenders will be opened by the tender inviting authority or his representative in presence of the attending tenderers or their authorized representatives at his office after 4.00 p.m. on 21.10.2022. If, the date of opening of tender be declared as public holiday for any administrative reason(s), the tenders shall be opened on the next working day at the same time and place.

**6. VALIDITY OF TENDER:**

The bid shall remain valid normally for twelve months from the date of opening of tender.

## 7. TIME FOR COMPLETION:

Time for completion of the work shall be 30 days from the date of Work Order / Lay out.

## 8. PROCEDURE FOR QUOTING RATES:

The rate should be quoted clearly in figure and in words in percentage basis, i.e., Less, at par, above on the estimate cost put to tender at the space provided for the purpose in the WBF 2911(i/ii).

## 9. EXECUTION OF AGREEMENT :

The successful bidders shall have to execute formal Agreement with Executive Engineer (Agri-Mech), Jalpaiguri (Agri-Mech) Division within 10 (ten) days from the date of issue of acceptance and formal work order with deposition of initial security deposit @ 2% of the value of work. Another 8% will be deducted from the agency's progressive bills so as to make it a total 10% Security deposit. The agreement shall be made in duplicate in W B Form no. 2911 on realization of price of two sets of tender document by online payment through GRIPS portal under the head of 0702-80-800-002-27-other items- other receipt as per Annexure-I from the office of the Executive Engineer (A-M), Jalpaiguri (A-M) Division (non-refundable). Failing to execute formal agreement within stipulated time, the formal work order will be treated as cancelled.

## 10. DEDUCTION OF TAX: -

Taxes will be deducted from the progressive bill as per Government rule in vogue.

## 11. SPECIAL ATTENTION:

Earnest Money of unsuccessful bidders will be released after finalization of tender. Security deposit of successful bidder will be released after six months from the date of successful completion of the work recommended by the concerned Assistant Engineer (Agri-Mech). The tender inviting authority reserve the right to accept or reject any tender or split the work without assigning any reason whatsoever. Canvassing in any form will render oneself disqualify from participating the tender.

*Sit A. Saha*

Assistant Engineer (A-M)  
Alipurduar (A-M) Sub-Division,  
Alipurduar

Memo No: 185 / (8)

Dated 11.10.2022.

Copy forwarded for information and wide circulation to: -

1. The Superintending Engineer (A-M), Siliguri (A-M) Circle, Shibmandir, Siliguri
2. The Executive Engineer (A-M), Jalpaiguri (A-M) Division, Jalpaiguri.
3. The Assistant Engineer (A-M) Siliguri / Jalpaiguri (A-M) Sub-Division, Siliguri / Jalpaiguri.
4. The Sabhadhipati, Alipurduar Zilla Parisad, Aipurduar.
5. The District Magistrate, Alipurduar.
6. The District Information & Culture Officer, Alipurduar
7. The D.I.O, Alipurduar. He is requested to upload a copy of this N.I.T. in the web portal.
8. Notice Board of this office.

*R. K. Saha*

Assistant Engineer (A-M)  
Alipurduar (A-M) Sub-Division,  
Alipurduar

## ANNEXURE-I

**Issued to;**

(NIT NO: 03 OF 2022-23 OF THE ASSISTANT ENGINEER (A-M), ALIPURDUAR (A-M) SUB-DIVISION)

(Circulated vide office memo no: 185 dated 11.10.2022 of AE(AM), Alipurduar(AM) Sub-Division)

SI No	Name of Work	Estimated cost put to Tender	Token earnest money to be deposited	cost of tender documents during agreement (In Rs.)	Last date & time of application	Last date & time of selling of tender documents	Last date & time of submission of tender/ opening of tender	Completion Time	Minimum credential
1	2	3	4	5	6	7	8	9	10
1	REPAIRING OF PIPE LINE OF DC II OF DAKSHIN KAMSING GOVT. OWNED AND OPERATED MAJOR RLI SCHEME IN THE DISTRICT OF ALIPURDUAR UNDER JALPAIGURI(A-M) DIVISION	Rs. 99,520.00	Rs. 2,500.00	Rs. 255.00	17.10.2022 upto 02:00 PM	17.10.2022 upto 04:00 PM	21.10.2022 upto 2:00 PM	30 (Thirty) days from the date of Layout	Rs. 40,000.00

  
Assistant Engineer (AM)  
Alipurduar (AM) Sub-Division  
Alipurduar

**ANNEXURE-II**


NIT NO: 03 OF 2022-23 OF THE ASSISTANT ENGINEER (A-M), ALIPURDUAR (A-M) SUB-DIVISION


**Issued to:****SCHEDULE FOR REPAIRING OF PIPE LINE OF DC II OF DAKSHIN KAMSING GOVT. OWNED AND OPERATED MAJOR RLI SCHEME IN THE DISTRICT OF ALIPURDUAR UNDER JALPAIGURI(A-M) DIVISION.**

SL No	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. ( WRDD-2018/CH-2.10/item no. 1)	m <sup>3</sup>	140.00	99.01	Rs.13,861.40
2	Repair of puncture/holes of any size in existing P.V.C. Pipeline of HDTW/MDTW/RLI by placing half round P.V.C. Pipe section of required 200 mm dia PVC Pipe 140 mm dia PVC Pipe ( WRDD-2018/CH-2.40/item no. 2/ii/iii)	Nos	20.00	83.92	Rs.1,678.40
		Nos	35.00	59.41	Rs.2,079.35
3	Laying of UPVC pipes of different diameters within field trenches in curve / straight line using PVC fittings, viz. Bend, Tee, Reducer etc. and making leak- ( WRDD/CH-2.20/item no. 1(A)(iii) (iii) 140mm dia Pipe	m	50.00	10.14	Rs.507.00
4	Labour charge for replacement of damage P.V.C. Pipe of any length in the Pipe line of HDTW / MDTW / RLI with a new piece of pipe to be issued departmentally after taking out the damage pipe from the existing pipe line by cutting with hacksaw and joining the new pipe with the existing pipe using two numbers couplers of 4 Kg./cm <sup>2</sup> capacity after roughening up surface with wire brush, emery paper and applying the solvent cement (cost inclusive) to make the joint leakproof as per direction of Engineer-in-Charge excluding supply of the couplers as per I.S.I. Specification at site and transporting departmentally issued pipes from Sub-Divisional Store to the Site. 140 mm dia PVC Pipe ( WRDD-2018/CH-2.40/item no. 3(iv)	Set	50.00	199.91	Rs.9,995.50
5	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavaion of foundation ( WRDD-2018/CH-2.10/item no. 2)	m <sup>3</sup>	68.26	66.01	Rs.4,506.07
6	Taking out the condemned 150mm dia NTP/TP/Alfa Alfa valve from 150 mm dia MS/GI pipe of existing spout chamber by careful chiseling with least disturbance to the existing system of structure up to required limit and fitting fixing of new one wih 150 mm dia MS/ GI pipe in proper position of the spout chamber using havoc zinc jute so as to make the joint leak proof including mending good all damages and retaining back the condemt materials at store as per direction of E.I.C. 150mm dia NTP valve ( WRDD-2018/CH-2.30/item no. 11)	Each	10.00	81.09	Rs.810.90
7	Fitting and fixing of M.S./G.I./C.I.accessories and special in pipe line (accessories & special to be supplied departmentally) including supply of jointing materials viz.rubber insertion, nuts & bolts, havoc Zink (Zink Oxide) complete as per direction of Engineer-in-Charge. (xxviii) 150mm. dia. C.I. sluice valve( WRDD-2018/CH-2.0/item no. 2(xxviii)	Each	6.00	54.69	Rs.328.14

SL No	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.	
8	Dismantling all types of plain cement concrete works, stacking all serviceable materials at site and removing rubbish as directed within a lead of 75m in ground floor. (a) up to 150 mm thick. (PWD-2017/P-10/It-2(a))	m <sup>3</sup>	1.47	939.00	Rs.1,379.16	
9	sand filling in foundation or plinth in layers not exceeding 15 cm as directed and considering the same by through saturation with water and ramming complete including the cost of supply of sand A) With local sand (PWD-2017/P-2/It-4)	%m <sup>3</sup>	1.40	52107.00	Rs.731.78	
10	Single brick flat soling of picked Jhama bricks including ramming and dressing bed to proper level and filling joints with powdered earth or local sand. (PWD-2017/P-14/item no.1)	m <sup>2</sup>	18.73	323.00	Rs.6,048.18	
11	Ordinary Cement concrete(mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering & reinforcement if any, in ground floor as per relevant IS code. PWD-2017/P-24/item no.4(b).	m <sup>3</sup>	1.90	3925.00	Rs.7,457.50	
12	Hire and labour charges for shuttering with centering and necessary staging upto 4 metre using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor). 25 mm. to 37.5 mm. thick wooden shuttering. PWD-2017/P-3/item no.6(a)	m <sup>2</sup>	4.63	328.00	Rs.1,518.64	
13	Brick work in cement mortar (1 : 6) with first class kiln burnt bricks including racking out joints, scaffolding and other incidental works etc. complete. (a) In chamber PWD-2017/P-15/item no. 8(a)	m <sup>3</sup>	4.13	4845.00	Rs.20,021.96	
14	12.5 cm. thick 1st class brickwork in cement mortar (1 : 4) in ground floor including, scaffolding, racking out joints etc. complete. PWD-2017/P-16/item no. 16	m <sup>2</sup>	4.50	668.00	Rs.3,006.00	
15	Plaster (to wall, floor ceiling etc) with sand and cement mortar including rounding off or chamfering corners, as directed and racking out joints or roughening of concrete surface including throating, nosing and drip course as necessary at ground floor. (i) with (1:4) cement mortar. (c) 15 mm. thick plaster. PWD-2017/P-189/item no. 1(ii)(b)	m <sup>2</sup>	50.93	154.00	Rs.7,842.45	
16	Neat cement punning about 1.5 mm. thick in wall dado, floor, drain, door and window sill etc. complete. PWD-2017/P-192/item no. 15	m <sup>2</sup>	50.93	34.00	Rs.1,731.45	
					Total	Rs.83,503.88
					Add 18% GST	Rs.15,030.69
					Sub Total	Rs.98,534.57
					Add CESS 1%	Rs.985.35
					Total	Rs.99,519.92
					Say	Rs.99,520.00

Rupees Ninety Nine Thousand Five Hundred Twenty only

  
11.10.22  
Junior Engineer(M)  
Alipuruar(AM) Sub Division  
Alipurduar

  
Assistant Engineer(AM)  
Alipuruar(AM) Sub Division  
Alipurduar